

WIND ENGINEERING STUDY
OF THE
MOBILE SERVICE TOWER AND SPACE SHUTTLE
FOR SLC-6, VANDENBERG AFB, CALIFORNIA

by

G. K. Kiely*
J. E. Cermak**
J. A. Peterka***

for

Sverdup and Parcel and Associates, Inc.
800 North 12th Boulevard
St. Louis, Missouri 63101

Fluid Mechanics and Wind Engineering Program
Fluid Dynamics and Diffusion Laboratory
Department of Civil Engineering
Colorado State University
Fort Collins, Colorado 80523

May 1979

*Graduate Research Assistant
**Director, Fluid Dynamics and Diffusion Laboratory
***Associate Professor

ACKNOWLEDGEMENTS

The support of Sverdrup & Parcel and Associates in carrying out this study is gratefully acknowledged.

Construction of the MST, PCR and auxiliary structures was accomplished by personnel of the Engineering Research Center Machine Shop.

Construction of the force and moment balances and data collection was accomplished principally by Max Pettago (Sr. Electronics Spec.) and Morgan Downing (Research Associate).

Mr. James A. Garrison supervised the photography and motion picture sessions.

Typing of this report was performed by Mrs. Arlene Nelson and Technical Typing staff.

TABLE OF CONTENTS

<u>Chapter</u>		<u>Page</u>
	ACKNOWLEDGEMENTS	ii
	LIST OF FIGURES	iv
	LIST OF TABLES	vi
	LIST OF SYMBOLS	vii
1	INTRODUCTION	1
2	EXPERIMENTAL CONFIGURATION	3
	2.1 Wind Tunnel	3
	2.2 Models	3
	2.3 Test Configurations	4
	2.4 Experimental Arrangement	5
3	INSTRUMENTATION AND DATA ACQUISITION	7
	3.1 Flow Visualization	7
	3.2 Velocity Profiles	7
	3.3 Force and Moment Measurements	8
	3.4 Pressures on the MST	12
4	RESULTS	15
	4.1 Flow Visualization	15
	4.2 Velocity Profiles	16
	4.3 Forces and Moments on the MST	17
	4.4 Forces and Moments on the SSV	20
	4.5 Pressures on the MST	24
5	DISCUSSION	28
	5.1 Flow Visualization	28
	5.2 Velocity Profiles	30
	5.3 Forces and Moments on the MST	31
	5.4 Pressures on the MST	33
	5.5 Forces and Moments on the SSV	33
	REFERENCES	36
	FIGURES	37
	TABLES	88
	APPENDIX A	95
	APPENDIX B	102

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1	Environmental Wind Tunnel CSU	38
2	Tunnel Setup of MST	39
3	Coordinate System - MST	40
4a	MST - Pressure Taps	41
4b	MST - Pressure Taps	42
4c	MST - Pressure Taps	43
4d	MST - Pressure Taps	44
4e	MST - Pressure Taps	45
4f	MST - Pressure Taps	46
4g	MST - Pressure Taps	47
4h	MST - Pressure Model (Photograph)	48
4j	MST - Pressure Model (Photograph)	49
4k	Data Sampling Time Verification	50
4l	Peak Pressure Contours - External	51
4m	Peak Pressure Contours - External	52
4n	Peak Pressure Contours - External	53
4p	Peak Pressure Contours - Internal	54
4q	Peak Pressure Contours - Internal	55
4r	Peak Pressure Contours - Internal	56
4s	Peak Pressure Contours - Roof	57
5a	Two-Component Force Balance (photograph)	58
5b	Two-Component Force Balance (photograph)	59
5c	Two-Component Force Balance (diagramatic)	60
5d	The Force Diagram of the Dynamometer	61

5e	Free Body Diagram 1	61
5f	Free Body Diagram 2	61
5g	Two-Component Force Balance Calibration	62
6a	Three-Component Moment Balance (photograph)	63
6b	Three-Component Moment Balance (photograph)	64
6c	Three-Component Moment Balance (diagramatic)	65
6d	Three-Component Moment Balance Calibration	66
7a	Configuration 1 - MST	67
7b	Configuration 1A - MST	68
7c	Configuration 2 - MST	69
7d	Configuration 3 - MST	70
7e	Configuration 4 - MST	71
7f	Configuration 5 - MST	72
7g	MST in Wind Tunnel (looking upstream-photograph) . . .	73
8a	Configuration A - SSV	74
8aa	Configuration A - SSV (photograph)	75
8b	Configuration B - SSV	76
8bb	Configuration B - SSV (photograph)	77
8c	Configuration C - SSV	78
8cc	Configuration C - SSV (photograph)	79
8d	Configuration E-2 ₂ - SSV	80
8e	Configuration E-2 - SSV	81
8f	Configuration D-2 - SSV	82
9	Strategic Velocity Positions	83
10	Locations for Velocity Profiles	84
11	Velocity and Turbulence Profiles	85
12	Velocity and Turbulence Profiles	86
13	Location of Wind Angle to give Maximum Moments on SSV	87

LIST OF TABLES

<u>Table</u>		<u>Page</u>
a	MST Configurations vs. Wind Angle	4
b	SSV Configurations vs. Wind Angle	5
c	Motion Picture Scene Guide	15
d	Definition of MST Force and Moment Coefficients	17
e	Definition of SSV Force and Moment Coefficients	20
1	MST Cladding Loads	89
2	Forces and Moments on Space Shuttle (SSV)	90
3	Wind Velocities and Turbulence Intensities SSV - Configuration B	92

LIST OF SYMBOLS

<u>Symbol</u>	<u>Definition</u>
U	Local mean velocity
H	Characteristic dimension (building Height)
B	Characteristic dimension
A	Characteristic Area
ν, ρ	Kinematic viscosity and density of approach flow
$\frac{UD}{\nu}$	Reynolds number.
E	Mean voltage
A, B, n	constants
U_{rms}	Root-mean-square of fluctuating velocity
E_{rms}	Root-mean-square of fluctuating voltage
U_H	Reference mean velocity at top of building
U_{30}	Reference mean velocity corresponding to 30 ft full-scale
X, Y	Horizontal coordinates
Z	Height above surface
δ	Height of boundary layer
T_u	Turbulence intensity $\frac{U_{rms}}{U_H}$
$C_{P_{mean30}}$	Mean pressure coefficient, $\frac{(p-p_{30})_{mean}}{0.5 \rho U_{30}^2}$
$C_{P_{rms30}}$	Root-mean-square pressure coefficient, $\frac{((p-p_{30}) - (p-p_{30})_{mean})_{rms}}{0.5 \rho U_{30}^2}$
$C_{P_{max30}}$	Peak maximum pressure coefficient, $\frac{(p-p_{30})_{max}}{0.5 \rho U_{30}^2}$

Symbol

Definition

$C_{P_{min_{30}}}$	Peak minimum pressure coefficient, $\frac{(p-p_{30})_{min}}{0.5 \rho U_{30}^2}$
$()_{min}$	Minimum value during data record
$()_{max}$	Maximum value during data record
p	Fluctuating pressure at a pressure tap on the structure
P_{30}	Static pressure in the wind tunnel corresponding to 30 ft in full scale (i.e., 3.6 in. in model scale)
A_1	The projected frontal area of orbiter and external tank and boosters viewed from the wind direction 270°.
H_1	
B_1	
A_2	The projected frontal area of orbiter only
H_2	The height of orbiter
B_2	The radius of the external tank
A_3	The projected area of external tank
H_3	The height from top of launch pad to top of external tank
B_3	The radius of the external tank

Abbreviations

SSV	Space Shuttle Vehicle
ET	External Tank
LM	Launch Mount
MST	Mobile Service Tower
PCR	Payload Change Room
AT	Access Tower

1. INTRODUCTION

The magnitude of the wind induced loads on the Space Shuttle in a stationary ground position is a significant factor in its launch-site assembly and support against wind and design of the surrounding buildings. Factors influencing the loads are 1) meteorological variables, such as approach wind speed and direction, and 2) the geometry and configuration of the Shuttle and surrounding buildings.

The purpose of this study was to determine the flow patterns and forces and moments on the Space Shuttle and Mobile Service Tower: The study was divided into five different parts as follows:

- A) mean velocity and turbulence profiles of the simulated atmospheric boundary layer
- B) forces and moments on the Mobile Service Tower (with no other buildings in place)
- C) pressure measurements on the Mobile Service Tower using 100 external and 56 internal pressure taps
- D) forces and moments on the Space Shuttle in six different configurations and
- E) flow visualization studies by addition of smoke was recorded on still and motion pictures.

The study was performed in the Environmental Wind Tunnel in the Fluid Dynamics and Diffusion Laboratory. This facility permitted modeling of the Space Shuttle and auxiliary buildings to a scale of 1:100. Modeling of the wind flow over and around these complex geometries requires special consideration of flow conditions in order to guarantee similitude between model and prototype. A detailed discussion of the

similarity requirements can be found in References (1), (2) and (3).

In general, the requirements are that the model and prototype be geometrically similar, that the approach mean velocity at the model location have a vertical profile shape similar to the full-scale flow, and that the turbulence characteristics of the flows be similar. For sufficiently high Reynolds number ($> 2 \times 10^4$) the airflow patterns about bluff bodies will be essentially constant for a large range of Reynolds numbers. Typical values encountered are 10^6 - 10^7 for the full-scale and 10^4 - 10^5 for the wind tunnel model. In this range acceptable flow similarity is achieved without precise Reynolds numbers equality.

2. EXPERIMENTAL CONFIGURATION

2.1 Wind Tunnel

The study was performed in the Environmental Wind Tunnel located in the Fluid Dynamics and Diffusion Laboratory at Colorado State University. The wind tunnel is an open-circuit facility driven by a 50 hp variable speed propeller. The test section is nominally 12 ft wide, 7 ft high and 57 ft long fed through a 3.35:1 contraction ratio. The roof is adjustable to maintain a zero pressure gradient along the test section. The mean velocity can be adjusted continuously from 1 to 30 fps. A diagram of the wind tunnel is shown in Figure 1.

2.2 Models

In the determination of forces and moments on the MST building, scaled models made of aluminum and plastic were used. The model was mounted on an aluminum base plate located below the tunnel floor. The base plate was securely fixed to a six-component strain gage force and moment balance (Figure 2). This arrangement was positioned on a turntable centered 45 ft from the test section entrance. The system was viscously damped by a set of masonite cross-fins moving in a viscous fluid to prevent motion of the model (Figure 2). The damping system worked satisfactorily and did not affect the magnitude of the mean forces and moments.

To determine the the local pressures on the MST building, a Plexiglas model containing 100 pressure taps on the outside faces and 56 taps on the inside was fabricated. The location of the taps on the structure are shown in Figures 4a to 4j (see Figure 3 for wall indentifications). Dimensions and elevations are given in both full-scale feet and model inches.

In order to determine the forces and moments on the Space Shuttle, two separate strain gage balances were used: One, a two-component force balance with a range of 0.02 to 3 lbs in both orthogonal directions (Figures 5a and 5b); the other, a three-component moment balance with a range of 0.01 to 20 inch-lb (Figures 6a and 6b). Each was separately set in position below the tunnel floor in a layout similar to that of the six-component force balance (Figure 2). The model of the orbiter and external tanks was mounted on an aluminum base plate located below the tunnel floor. The base plate was securely fixed to either the two-component force balance or the three-component moment balance. As with the MST building, the different Space Shuttle configurations were viscously damped by sets of brass or Plexiglas fins (Figures 5 and 6). The damping system worked satisfactorily and did not affect the magnitude of the mean forces and moments.

2.3 Test Configurations

For the force and moment measurements on the MST building, measurements were made for six different configurations and five different angles of wind approach (see Figure 3 for coordinate system). This is a total of thirty individual runs. The configurations are shown in Figures 7a to 7f.

Table a
MST Configurations vs. Wind Angle

Configuration	Angle of Wind
1	90, 135, 180, 225, 270
1A	"
2	"
3	"
4	"
5	"

For the force and moment measurements on the Space Shuttle, measurements were made for six different configurations and five different angles of wind approach.

Table b
SSV Configurations vs. Wind Angle

Configuration	Angle of Wind
A	90, 135, 180, 225, 270
B	"
C	"
E-2	"
E-2 ₂	"
D-2	"

These configurations are depicted in Figures 8a to 8f. All configurations requiring an MST model used configuration 5 of the MST.

The pressure measurements on the MST were done on the 272 ft high building with the sides fully clad and identical to configuration 5 of Table a (Figure 7f). A photograph of the pressure model is shown in Figures 4g and 4h.

2.4 Experimental Arrangement

The models were mounted on a 12 ft diameter turntable centered 45 ft downstream from the test section. The turntable was calibrated to indicate azimuthal orientation to 0.3 degrees. The region upstream from the model was covered with 1/4 in. thick pegboard with 1/4 in. diameter, 1/2 in. long wooden pegs inserted to form a pattern of roughness which would produce the desired approach flow. Spires were installed at the test section entrance to provide a thicker boundary layer than would otherwise be available. The spires were approximately triangularly shaped

pieces of 1/2 in. thick plywood 6 in. wide at the base and 1 in. wide at the top, extending from the floor to the top of the test section. They were placed so that the broad side intercepted the flow. Splitter plates, triangular in cross-section and made to fit the shape of the spires, were placed downstream from, but in contact with, the spires to form streamlined obstructions in the airflow path. An additional flow trip consisting of 7 in. high bricks standing on end spaced approximately at 1 ft was placed 8 ft upstream of the spires in the intake transition section. This combination of spires and trip provided a boundary layer thickness of approximately 4 ft and an approach velocity profile power-law exponent similar to that for flow over smooth terrain. A photograph of the MST building in the tunnel is shown in Figure 7g.

Velocity profiles were taken at 4 locations as shown in Figures 10, 11 and 12. These 4 velocity profiles were taken to define the approach flow in the absence of buildings.

Velocity measurements were made at 6 strategic locations as indicated in Figure 9. These were taken to discern the flow velocity behavior in the vicinity of the SSV complex.

3. INSTRUMENTATION AND DATA ACQUISITION

3.1 Flow Visualization

Making the airflow visible in and around the different models is helpful in defining areas of high or low velocity, flow channeling or other flow characteristics which may increase or decrease loading. Titanium tetrachloride smoke was released from sources on and near the model to make the flow lines visible to the eye and to make it possible to obtain motion picture records of the tests. A guide to the motion picture scenes is given in Table c. Results of these smoke studies are discussed in Section 4.1 and the conclusions stated in Section 5.1.

3.2 Velocity Profiles

Mean velocity and turbulence intensity profiles were measured upstream of the model to determine the characteristics of the approach wind. Measurements were also taken at the center of the turntable and the profile data is shown in Figures 10, 11 and 12.

Velocity measurements were made with a single hot-wire anemometer. The probe was mounted with its axis horizontal and was supported from a vertical traverse which was positioned behind the model so as not to create a disturbance near the model. The instrumentation used was a Thermo Systems constant temperature anemometer (model 1050) with a .001 in. diameter platinum film sensing element .02 in. long. Output from the anemometer was fed to an on-line data acquisition system, consisting of a Hewlett-Packard 21 MX computer, disc unit, card reader, printer, Digi-Data digital tape drive and a Preston Scientific analog to digital converter. The data was processed immediately into mean velocities, turbulence intensities and corresponding heights and stored on a computer disc for printout and further analysis.

Calibration of the hot-wire was performed using a Thermo Systems Calibrator (Model 1125). The calibration data were fit to a variable exponent King's Law relationship,

$$E^2 = A + BU^n$$

where E is the hot-wire output voltage, U the approach velocity and A , B and n are effective coefficients selected to fit the data. The above relationship was used to determine the mean velocity at measurement points using the measured mean voltage data. The fluctuating velocity in the form U_{rms} (root-mean square velocity) was obtained from

$$U_{rms} = \frac{2E E_{rms}}{BnU^{n-1}}$$

where E_{rms} is the root-mean square voltage output from the anemometer. The turbulence intensity is then the ratio U_{rms}/U_H .

3.3 Force and Moment Measurements

For the force and moment measurements of the MST building an Inca six-component strain gage balance was used. Wind forces and moments were measured in the X , Y and Z directions in a coordinate system fixed to the MST building as shown in Figure 3. The force F_Z was not recorded. Each strain-gage bridge of the Inca balance was monitored by a Honeywell Acudata 118 gage control/amplifier unit for signal conditioning. These units are characterized by a very stable excitation voltage and amplifier gain. Output from the Honeywell signal conditioners was fed to an on-line, analog to digital conversion unit. Calibration of the balance was accomplished in a test rig in which known forces and moments could be applied to the balance. From static (weight-over-pulley) calibration results a calibration matrix was developed for reducing the mean output of the strain gages. Load and

strain relationship is strictly linear for the range of loads applied in these tests. The balance capacity is 50 lbs force and 300 in.-lbs moment. Values measured during the MST tests were 4.33 lbs maximum force and 103 in.-lbs maximum moment (the latter corrected to floor level).

For the force measurements on the Space Shuttle a two-component force balance with a range of 0.02 to 3 lbs, was used. This recorded the forces in two orthogonal directions, i.e. F_y and F_x (or drag and lateral forces respectively). This balance is shown in Figures 5a to 5c. The balance measures accurately the total drag and the total lateral force on the Space Shuttle regardless of where the resultant of the drag or lift force is applied. The balance is, of course, a two-dimensional instrument but the mathematical verification is most simply explained by considering only the drag measuring section. That is, consider the balance is one-dimensional. Because of minute interactions between F_x and F_y the following proof is valid.

Figure 5d shows a constant resultant force applied at a position, ℓ , on a stiff rod which is inserted into the vertical receptical of the transducer. The force pushes the rod through a horizontal displacement, e . L is a constant, from level A to the bearings at level B. Consider ℓ as a variable, from level B to the resultant position of the force. Two shearing forces, V_1 and V_2 , and two restoring moments M_1 and M_2 , are exerted on leg 1 and leg 2 respectively. T_{1A} is the tension in leg 1 and T_{2A} the compression in leg 2. W is the total weight of the instrument, considered as a concentrated load at the center.

Consider the free body diagram 1 shown in Figure 5e:

$$\Sigma F_x = 0 \quad (1)$$

then

$$F = P_1 + P_2 \quad (2)$$

and

$$\Sigma F_y = 0 \quad (3)$$

hence

$$W = T_{2B} - T_{1B} \quad (4)$$

Taking moments about hinge 1 gives:

$$\Sigma M_1 = 0 \quad (5)$$

then

$$T_{2B} = \frac{F\ell}{x} + \frac{W}{2} \quad (6)$$

thus

$$T_{1B} = \frac{F\ell}{x} - \frac{W}{2} \quad (7)$$

Now consider the free body diagram 2 shown in Figure 5f:

$$e_1 = e_2 = e \quad (8)$$

from

$$\Sigma M_{A1} = 0 \quad (9)$$

$$M_1 = P_1L - T_{1B} e \quad (10)$$

and

$$\Sigma M_{A2} = 0 \quad (11)$$

$$M_2 = P_2L + T_{2B} e \quad (12)$$

The total moment is

$$M_1 + M_2 = L (P_1 + P_2) + e (T_{2B} - T_{1B}) \quad (13)$$

or

$$M_1 + M_2 = LF + eW \quad (14)$$

but,

$$L \gg e \quad \text{and} \quad F \approx 0(w), \quad \text{therefore} \quad LF \gg eW$$

thus,

$$M_1 + M_2 \approx LF. \quad (15)$$

From Equation (15), the conclusion can be drawn that the total moment depends only on the constant resultant force F and the constant distance L .

The above results were verified experimentally for F ranging from 0.1 lbs to 3 lbs and for L ranging from 2 to 18 inches. Figure 5g is the calibration curve which was obtained by applying the various loads at one position of the stiff rod. The response did not change when the load was shifted to another position on the rod. Figure 5a shows the balance ready to be set in place in the wind tunnel.

For the moment measurements on the Space Shuttle a three-component moment balance with a range of 0.01 to 20 in.-lb was used. The balance measured the M_x , M_y , M_z moments. It is shown in Figures 6a to 6b. The mathematical proof of this instrument is related to the proof already given for the two-component force balance. As in the case of the force balance the operation of the moment balance was verified experimentally. Figure 6d is a plot of the calibration of the three quantities M_x , M_y and M_z . It is noted from these that each strain gage system (e.g., M_x)

were different, due to different stiffness for each component sense. It was also verified that the interactions between each of the three channels were minute.

In both the force and moment balances, it was found effective to install damping mechanisms. As in the six component inca-balance the damping system worked satisfactorily and did not affect the magnitude of the mean forces and moments.

3.4 Pressures on the MST

Mean and fluctuating pressures were obtained at each of the 100 external pressure taps and 56 internal on the MST Plexiglas model. Data was obtained for 5 wind directions (90, 135, 280, 225, and 270 degrees). Figures 4h and 4j are pictorials of the MST pressure study building. The model was made of 1/4 in. Plexiglas with brass tubes 1/8 in. O.D. inserted in its walls in a vertical position and on the roof in a horizontal position. Each brass tube was drilled through at desired locations to give a pressure tap on both the inside and outside (when either was blocked off). Pressure tap locations are marked in black on the back wall of Figure 4j and are shown diagrammatically in Figures 4a to 4g. The brass tubes were connected to plastic tubing which in turn were connected to a pressure switch mounted below the tunnel floor. The pressure switch has the capacity of working with 76 pressure taps, however in this case it was operated with a maximum of 16 (this number being the number of vertical brass tubes). The switch was designed and built in the Fluid Dynamics and Diffusion Laboratory to minimize the attenuation of pressure fluctuations across the switch. Each of the 16 pressure taps was directed in turn by the switch to one of four pressure transducers mounted close to the switch. Four pressure input taps used for transmitting building

surface pressures were connected to a common tube leading outside the wind tunnel. This arrangement provides both a means of performing in-place calibration of the transducers and, by connecting this tube to a pitot tube mounted inside the wind tunnel, a means of automatically monitoring the tunnel speed. The switch is operated by means of a shaft projecting through the floor of the wind tunnel. A computer-controlled stopping motor stepped the switch into each of the 5 required positions. The computer monitored switch position but a digital readout of position was also provided at the wind tunnel.

The pressure transducers used are Statham differential strain gage transducers (Model PM 283TC) with a 0.15 psid range. They were selected because of their stability and linearity in the required working range. Reference pressures were obtained by connecting the reference sides of the four transducers, using plastic tubing, to the static side of a pitot tube mounted in the wind tunnel free stream above the model building. In this way the transducer measured the instantaneous difference between the local pressures on the surface of the building and the static pressure in the free stream above the model.

Each pressure transducer contains a built-in bridge similar to a Wheatstone Bridge. The bridge is monitored by a Honeywell Accudata 118 Gage Control/Amplifier unit which provides excitation to the transducer bridge and amplifies the bridge output. These instruments are characterized by a very stable excitation voltage and amplifier gain. Output from the Honeywell signal conditioners was fed to an on-line data acquisition system consisting of a Hewlett-Packard 21 MX computer, disc unit, card reader, printer, Digi-Data digital tape drive and a Preston Scientific analog-to-digital converter. The data were processed immediately into

pressure coefficient form as described in Section 4.5 and stored for printout or further analysis.

All four transducers were recorded simultaneously for 16 seconds at a 250 sample per second rate. The results of an experiment to determine the length of record required to obtain stable mean and rms (root-mean-square) pressures and to determine the overall accuracy of the pressure data acquisition system is shown in Figure 4k. A typical pressure port record was integrated for a number of different time periods to obtain the data shown. Examination of a large number of pressure taps showed that the overall accuracy for a 16 second period was, in pressure coefficient form, 0.03 for mean pressures, 0.1 for peak pressures, and 0.01 for rms pressures. Pressure coefficients are defined in Section 4.5. Because tube lengths required to reach the upper portions of the structure were longer than normally used with this data acquisition system, frequency attenuation in the pressure tubes may result in slight underestimation of peak local pressures on the upper third of the MST.

4. RESULTS

4.1 Flow Visualization

A film is included as part of this report showing the characteristics of flow about the structures using smoke to make the flow visible. A listing of the contents of the film is shown in Table c.

Table c
MOTION PICTURE SCENE GUIDE

Run #	SSV Configuration	Wind Direction
1	A	90°
2	B	90°
3	C	90°
4	E-2 ₂	90°
5	A	135°
6	B	135°
7	C	135°
8	E-2 ₂	135°
9	A	180°
10	B	180°
11	C	180°
12	E-2 ₂	180°
13	A	225°
14	B	225°
15	C	225°
16	E-2 ₂	225°
17	A	270°
18	B	270°
19	C	270°
20	E-2 ₂	270°

Length = 1085 ft
Running time = 30 min

4.2 Velocity Profiles

Velocity and turbulence profiles are shown in Figures 11 and 12. These profiles were taken upstream from the model and are characteristic of the boundary-layer approaching the model. As shown in Figure 11, the boundary-layer thickness, δ , was 50 in. The corresponding prototype value of δ for this study is 415 ft. Because of the complex terrain near the complex, the prototype value is not known, but this value was established as a reasonable height for this study. The mean velocity profile has the form

$$\frac{U}{U_{\delta}} = \left(\frac{z}{\delta}\right)^p .$$

The exponent p for the approach flow established for this study is shown in Figure 11.

The profile of longitudinal turbulence intensity is shown in Figures 11 and 12. The turbulence intensities are appropriate for the approach mean velocity profile selected. For the purpose of this report, turbulence intensity is defined as the root-mean-square about the mean of the longitudinal velocity fluctuations divided by the reference mean velocity U_H at the top of the building

$$Tu = \frac{U_{rms}}{U_H} .$$

Mean velocity U/U_H , turbulence intensity U_{rms}/U_H , and largest effective gust at strategic measuring positions shown in Figure 9 were obtained to show velocity magnitudes near the SSV with MST and PCR in place. The 'peak' velocity representing roughly the largest effective gust velocity was calculated using:

$$U_{pk} = \frac{U + 3U_{rms}}{U_H} .$$

A discussion of these values is given in Section 5.2 while data are listed in Table 4 for 5 wind directions.

4.3 Forces and Moments on MST

The computer output in Appendix A shows the forces and moments experienced by the model. The corresponding coefficients are with respect to a dynamic pressure of $1/2 \rho U_{30}^2$ where U_{30} is the velocity at 30 ft in the full-scale. All coefficients are with respect to the pertinent wall areas and model dimensions used for each configuration.

The nondimensional coefficients pertinent to the MST study are defined in Table d.

Table d
Definition of MST Force and Moment Coefficients

C_{F_x}	=	$F_x / q_{30} WH$
C_{F_y}	=	$F_y / q_{30} LH$
C_{M_x}	=	$M_x / q_{30} LH^2$
C_{M_y}	=	$M_y / q_{30} WH^2$
C_{M_z}	=	$M_z / q_{30} LH^2$
q_{30}	=	$1/2 \rho U_{30}^2$

The following is a list of values used in the model tests.

$$U_H = 29.49 \text{ ft/sec (velocity at the top of building)}$$

$$U_{30} = 0.69 U_H = 20.38 \text{ ft/sec}$$

$$q_{30} = 1/2 \rho U_{30}^2 = 0.415 \text{ lb/ft}^2$$

W = 9.9 in.	}	model values Configurations 1 to 4
H = 37.8 in.		
L = 16.26 in.		
W = 9.9 in.	}	model values Configuration 5
H = 33.0 in.		
L = 16.26 in.		

The only difference to the values for configurations 1 to 4 and 5 is the height:

$$H = 33.0 \text{ in.}$$

Note that for all MST load measurements, U_H was

$$U_H = U_{37.8}$$

i.e., the height at which the pitot tube was placed in the wind tunnel and was held constant for the duration of the MST experiments (including configuration 5).

Sample calculations are included in the following pages.

AIR DENSITY

The density of air is dependent on the barometric pressure and temperature. It may be evaluated using the following relationship:

$$\text{Density} = \frac{\text{Barometric pressure in inches}}{(\text{Absolute temp}) \times 24.29697} \text{ :slugs/ft}^3$$

$$\text{Absolute temp} = \text{temperature in } ^\circ\text{F} + 459.69$$

SAMPLE FORCE AND MOMENT CALCULATIONS

The following example is used to explain the procedure for calculating full scale the forces and moments on the MST. Assume the following conditions at the site:

$$\text{Temperature} = 60^\circ\text{F}$$

Barometric pressure = 30.3 in.

Wind speed at 30 ft = 80 mph = 117.3 ft/sec

$$\text{Density} = \frac{30.3}{519.69 \times 24.297} = 0.0024 \text{ slugs/ft}^3$$

Building Dimensions: (full-scale)

H = 315 ft (ground level to roof level)

W = 82.5 ft (narrow side of building)

L = 135.5 ft (large side of building)

Configuration 1: wind approach angle 90°

Question--

What are the along wind force and the along wind overturning moment?

Step 1: $F_y = ?$ (along wind force)

$M_x = ?$ (along wind moment)

Step 2: $F_y = C_{F_y} q_{30} L H$

$M_x = C_{M_x} q_{30} L H^2$

Step 3: Dynamic pressure $q_{30} = ?$

$$q_{30} = 1/2 \rho U_{30}^2$$

$$q_{30} = 1/2 \times 0.0024 \times 117.3^2 = 16.51 \text{ lbs/ft}^2$$

Step 4: $F_y = C_{F_y} q_{30} L H$

Computer output, Appendix A, read $C_{F_y} = 2.25$

$$F_y = 2.25 \times 16.51 \times 135.5 \times 315 = 1.5856 \times 10^6 \text{ lbs}$$

$$= 1585.6 \text{ kips}$$

Step 5: $M_x = C_{M_x} q_{30} L H^2$

Computer output, Appendix A, read $C_{M_x} = -1.04$

$$M_x = -1.04 \times 16.51 \times 135.5 \times 315^2 = -230.9 \times 10^3 \text{ kip-ft}$$

4.4 Forces and Moments on the S.S.V.

The forces and moments measured on the six configurations pertinent to the SSV are shown in Table 2. The corresponding coefficients are with respect to the dynamic pressure of $1/2 \rho U_{30}^2$ (as in the MST study) where U_{30} is the velocity at 30 ft, in the full scale. The coefficients are based on the reference lengths and areas respective to the particular configuration. The nondimensional coefficients pertinent to the SSV study are shown in Table e.

Table e
Definition of SSV Force and Moment Coefficients

$$C_{F_x} = \frac{F_x}{q_{30} A_i}$$

$$C_{F_y} = \frac{F_y}{q_{30} A_i}$$

$$C_{M_x} = \frac{M_x}{q_{30} A_i H_i}$$

$$C_{M_y} = \frac{M_y}{q_{30} A_i H_i}$$

$$C_{M_z} = \frac{M_z}{q_{30} A_i B_i}$$

$A_i H_i$ and B_i for the respective configurations are given on the following page.

$i = 1, 2$ or 3 .

The H_i value is measured from the top of the launch-mount.

The following is a list of values estimated from the model and their corresponding full-scale values (the latter not necessarily the exact values).

$$U_{3.6 \text{ in.}} (\text{model}) = U_{30} (\text{full-scale}) = 20.38 \text{ ft/sec}$$

$$q_{30} = 1/2 \rho U_{30}^2 = .415 \text{ lbs/ft}^2$$

$\left\{ \begin{array}{l} A_1 = 116.2 \text{ in}^2 \\ H_1 = 20 \text{ in} \\ B_1 = 1.5 \text{ in} \end{array} \right.$	<p>model values configurations A, B, C, E-22</p>	$\left\{ \begin{array}{l} A_1 = 8069.4 \text{ ft}^2 \\ H_1 = 166.6 \text{ ft} \\ B_1 = 12.5 \text{ ft} \end{array} \right.$	<p>corresponding full-scale values</p>
$\left\{ \begin{array}{l} A_2 = 37 \text{ in}^2 \\ H_2 = 12 \text{ in} \\ B_2 = 1.5 \text{ in} \end{array} \right.$	<p>model values configuration E-2 (orbiter only)</p>	$\left\{ \begin{array}{l} A_2 = 2570 \text{ ft}^2 \\ H_2 = 100 \text{ ft} \\ B_2 = 12.5 \text{ ft} \end{array} \right.$	<p>corresponding full-scale values</p>
$\left\{ \begin{array}{l} A_3 = 60 \text{ in}^2 \\ H_3 = 20 \text{ in} \\ B_3 = 1.5 \text{ in} \end{array} \right.$	<p>model values configuration D-2 (tank only)</p>	$\left\{ \begin{array}{l} A_3 = 4167 \text{ ft}^2 \\ H_3 = 166.6 \text{ ft} \\ B_3 = 12.5 \text{ ft} \end{array} \right.$	<p>corresponding full-scale values.</p>

(See list of symbols for physical description of A_1 , A_2 , etc.)

During the experiments for load measurements on the SSV, the pitot tube was held at a constant height of 33.2 in. in the wind tunnel (i.e., at the MST building height). During data analysis this reference height velocity was converted to $U_{3.6 \text{ in.}}$ (i.e., U_{30} full-scale). The reason for this is that a better resolution of velocity is obtained near the free stream, which was at about 50 in. in the wind tunnel.

The procedure for calculating the full-scale forces and moments is similar to the example given in Section 4.3.

SAMPLE FORCE AND MOMENT CALCULATIONS - SSV

The following is an example used to explain the procedure of calculating the full-scale forces and moments on the SSV from the

force and moment coefficients of Table 2. Assume the following on-site conditions


Temperature = 60°F

Barometric pressure = 30.3 in.

Wind speed at 30 ft = 20 knots = 33.8 ft/sec

Density of air = $\frac{30.3}{519.69 \times 24.297} = .0024 \text{ slugs/ft}^3$

Question: Determine the drag force F_y and the corresponding moment M_x for configuration C at a wind angle of 225°. Also determine the force F_x and the corresponding moment M_y . Finally determine the torsional moment M_z for the same configuration and wind angle.



Right Hand Coordinate System

Note:

$+F_x$ causes $+M_y$

$+F_y$ causes $-M_x$.

} true because F_x and F_y
are applied physically above
the x and y axes.

Structure Dimensions (full scale)

$A = 8069.4 \text{ ft}^2$ (projected frontal area of orbiter & tank and boosters)

$H = 166.6 \text{ ft}$ (height from top of launch pad to top of external tank)

$B = 12.3 \text{ ft}$ (radius of external tank)

Determine: $F_x = ?$
 $F_y = ?$
 $M_x = ?$
 $M_y = ?$
 $M_z = ?$

Step 1. From Table 2.

Config.	Wind Angle	C_{F_x}	C_{F_y}	C_{M_x}	C_{M_y}	C_{M_z}
C	225°	-.93	-.80	.46	-.49	.45

Step 2. From Table e,

$$F_x = C_{F_x} q_{30} A$$

$$F_y = C_{F_y} q_{30} A$$

$$M_x = C_{M_x} q_{30} AH$$

$$M_y = C_{M_y} q_{30} AH$$

$$M_z = C_{M_z} q_{30} AB$$

Step 3. q_{30} = dynamic pressure at 30 ft

$$= 1/2 \rho U_{30}^2$$

$$= 1/2 \times .0024 \times (33.8)^2 = 1.370 \text{ lb/ft}^2$$

Step 4.

$$F_x = C_{F_x} q_{30} A$$

$$= -.93 \times 1.370 \times 8069.4 = -10281 \text{ lbs}$$

$$= -10.281 \text{ kips}$$

$$\begin{aligned}
 F_y &= C_{F_y} q_{30} A \\
 &= -.80 \times 1.37 \times 8069.4 = -8844 \text{ lbs} \\
 &= -8.84 \text{ kips}
 \end{aligned}$$

$$\begin{aligned}
 M_x &= C_{M_x} q_{30} AH \\
 &= .46 \times 1.37 \times 8069.4 \times 166.6 = 847217 \text{ ft-lbs} \\
 &= 847.22 \text{ ft-kips}
 \end{aligned}$$

$$\begin{aligned}
 M_y &= C_{M_y} q_{30} AH \\
 &= -.49 \times 1.37 \times 8069.4 \times 166.6 = -902470 \text{ ft-lbs} \\
 &= -902.47 \text{ ft-kips}
 \end{aligned}$$

$$\begin{aligned}
 M_z &= C_{M_z} q_{30} AB \\
 &= .45 \times 1.37 \times 8069.4 \times 12.5 = 62185.0 \text{ ft-lbs} \\
 &= 62.185 \text{ ft-kips}
 \end{aligned}$$

It is emphasized that the characteristic areas and lengths are those values measured from the model and then scaled to those of full scale.

4.5 Pressures on the MST

For each of the pressure taps examined at each wind direction, the data record was analyzed to obtain four separate pressure coefficients. The first is the mean pressure coefficient $C_{p_{\text{mean}}} = (p - p_{30})_{\text{mean}}$ where the symbols $0.5 \rho U_{30}^2$ are defined in the List of Symbols. It represents the mean of the instantaneous pressure difference between the building pressure tap and the static pressure in the wind tunnel above the building model, nondimensionalized by the dynamic pressure

$$0.5 \rho U_{30}^2$$

at the reference velocity position. This relationship produces a dimensionless coefficient which indicates that the mean pressure

difference between building and ambient wind at a given point on the structure is some fraction less or some fraction greater than the dynamic pressure at the 30 ft height in full-scale. Using the measured coefficient, prototype mean pressure values for any wind velocity may then be calculated.

The magnitude of the fluctuating pressure is obtained by the rms pressure coefficient

$$C_{p_{rms}} = \frac{\left((p-p_{30}) - (p-p_{30})_{\text{mean}} \right)_{rms}}{0.5 \rho U_{30}^2}$$

in which the numerator is the root-mean-square of the instantaneous pressure difference about the mean.

If the pressure fluctuations followed a Gaussian probability distribution, no additional data would be required to predict the frequency with which any given pressure level would be observed. However, the pressure fluctuations do not follow a Gaussian probability distribution so that additional information is required to show the extreme values of pressure expected. The peak maximum and peak minimum pressure coefficients are used to determine these values:

$$C_{p_{max}} = \frac{(p-p_{30})_{max}}{0.5 \rho U_{30}^2}$$

$$C_{p_{min}} = \frac{(p-p_{30})_{min}}{0.5 \rho U_{30}^2}$$

The values of $p-p_{30}$ which were digitized at 250 samples per second for 16 seconds, representing about one hour of time in the full-scale, are examined individually by the computer to obtain the most positive and

most negative values during the 16 second period. These are converted to $C_{p_{\max}}$ and $C_{p_{\min}}$ by nondimensionalizing with the 30 ft (full-scale) dynamic pressure.

The four pressure coefficients are calculated by the on-line data acquisition system computer and tabulated along with the approach wind azimuth in degrees from true north. The list of coefficients is included as Appendix B. The pressure tap code numbers used in the appendix are explained in Figures 4a to 4g.

To determine the largest peak loads acting at any point on the structure for cladding design purposes, the pressure coefficients for all wind directions were searched to obtain, at each pressure tap, the largest absolute value of peak pressure coefficient. Table 1 provides these pressure coefficients and associated wind directions. Included in Section 5.5 is an analysis of the coefficients of Table 1 including the maximum values obtained and where they occurred on the building. Because pressure differences across the shell were not measured simultaneously, peak pressures were not likely obtained at taps on opposite sides of the shell simultaneously. For this reason, peak pressures should be used with some care.

The pressure coefficients of Table 1 can be converted to full-scale loads by multiplication by a suitable reference pressure selected for the field site. This reference pressure is represented in the equations for pressure coefficients by the $0.5 \rho U_{30}^2$ denominator. This value is the dynamic pressure associated with an hourly mean wind at the reference velocity measurement position at 30 ft elevation. In general, the method of arriving at a design reference pressure for a particular

site involves selection of a design wind velocity, translation of the velocity to an hourly mean wind at the reference velocity location and conversion to a reference pressure. Selection of the design velocity can be made from statistical analysis of extreme wind data obtained at the site or selected from wind maps contained in the proposed wind loading code ANSI A58.1 of the American National Standards Institute (4). Gust factors to reduce gust winds to hourly mean winds is given in reference (5).


The reference pressure associated with the design hourly mean velocity at the reference velocity location can be used directly with the pressure coefficients to obtain mean and peak local wind loads for cladding design.

Local, instantaneous peak loads on the full-scale MST are obtained by multiplying the reference pressure by the peak coefficients of Table 1. The maximum psf load given at each tap location is the absolute value of the maximum value found in the tests, irrespective of its algebraic sign. For ease in visualizing the loads on the structure, contours of equal peak pressure coefficient shown in Table 1 have been plotted on developed elevation views of the structure, Figures 41 to 4s. It should be noted that coefficients shown in Figures 41 to 4s on inside and outside portions of a given panel are not developed simultaneously.


5. DISCUSSION

5.1 Flow Visualization

Flow visualization patterns on the six SSV configurations showed that flow separation characteristics near the corners of the structures might produce moderately high suctions near the corners.



For a wind angle of 270° on configuration A the flow patterns, sketched above indicate that the MST creates a stagnation zone in front of the SSV and it appears that the MST behaves essentially as if all its walls were solid. This observation is borne out in the results shown in Table 2 indicating very low forces and moments on the SSV. It is also noted in the flow visualization movie that again for a 270° wind and configurations A, E and D it appears that there are high velocity zones between the top of the PCR building and the roof of the MST allowing this accelerated flow to bear down on the top of the external tank as shown on next page.



High negative pressures are noticeable on the roof where the flow separates at the roof corners. Wind flow patterns near the base of the structures showed higher velocities due to openings in the MST than would be expected if these openings did exist. It was clearly noticeable that the flow structure was strongly three-dimensional in nature and does not lend itself to simple explanations. It was observed that vortices were shed from the




Fig. 8c Configuration C

wings of the SSV and also from the tanks in configuration C. This phenomenon appeared to occur at most wind directions between 180° and 270°.

5.2 Velocity Profiles

Table 3 gives the ratios of the mean, rms and peak wind velocities to the mean velocity at the top of the MST expressed as percentages. Six different locations were studied and measurements at each location were made for both a horizontal and vertical orientation of the measuring sensor axis. The sensor measures the magnitude of velocity vector component perpendicular to the sensor axis. Thus, in the horizontal mode (axis parallel to the x axis) the sensor measured the velocity component in the y-z plane, while in the vertical mode (axis parallel to the vertical axis) the sensor measured the velocity component in the x-y plane the horizontal velocity component. For brevity, the data are referred to as horizontal component data (sensor axis vertical) or as vertical component data (sensor axis horizontal). The measurement locations are shown in Figure 9. Location 1 its highest U_{mean}/U_H horizontal component from a 225° wind. Flow visualization observations indicated accelerated flow in this area. In magnitude, its value was 85 percent which means it is close to the value of U_H . The turbulence magnitudes for the horizontal component were about 8 percent for all wind directions indicating that the turbulence in this location is not dominant. Location 2 showed higher vertical than horizontal components of mean velocity. Location 4, situated close to the ground in the opening on the main wall of the MST indicated a very high velocity component in the y-z plane. This is commensurate with dominant vertical components at location 2. The highest turbulent intensities are experienced at

location 5 for a 270° wind. Location 5 is in the opening on the side wall of the MST and the vertical fluctuating component is up to 24 percent.

5.3 Forces and Moments on the MST


Appendix A contains the force and moment coefficients on the MST in isolation. For configuration 1 the highest coefficient is C_{F_y} for a wind direction of 270°. This magnitude is 2.36 compared with the corresponding magnitude of 2.25 for the 90° wind. The small difference in these values indicates that the total drag on the MST is almost the same whether the incident wind is onto the solid back face or into the front cavity face. These two "drag" coefficients have appreciably different magnitudes of moment coefficients (1.48 and 1.04 for 270° and 90° winds). This is due to differing heights of the center of action of the drag force on the MST caused by different geometry of the respective face.

Configuration 1A has the overhang sides and top covered. It is noticed that this does not appear to make much different to either the lateral or the drag forces or their corresponding moments. It is believed, based on flow visualization studies, that this covering may have a more noticeable different on the uplift values which were not measured.

Configurations 1 and 5 are identical buildings except that 1 has a height of 315 ft and 5 has a height of 272 ft. A general comparison of the coefficients indicates somewhat lower values for configuration 5 even with the smaller value of H used in the coefficient. This can be explained by the fact that configuration 1 is 43 ft higher up into the boundary layer where the mean wind velocities are higher, consequently a higher velocity wind is acting at these higher elevations. It is also noticed that the trends of the values are very similar allowing for this smaller magnitude of values in configuration 5.

Some interesting observations are noticed in a study of the coefficients relating to configurations 2, 3 and 4. Configuration 2 does not have cladding on the perimeter of the top 43 ft. As is expected this should have reduced force and moment coefficients in comparison to configuration 1. The magnitudes are, in general, reduced by about 10 percent.

Configuration 3 has a 30 percent porous back wall and no cladding on the top 43 ft perimeter. As is expected, this dramatically reduces the drag (C_{F_y}) by about 30 percent for the significant wind directions of 90° and 270° . It is also noticed that for the quartering wind directions of 135° and 225° the lateral force (C_{F_y}) is increased by about 20 percent. This increase beyond that of configuration 1 may have the following explanation.



For the 135° wind direction in particular the wind can enter through the back wall cavities, into the interior of the building. Consequently more wind force is exerted on wall 1a. This build-up of internal pressures does not occur in configuration 4 where these side walls are also 30 percent porosity. For configuration 4 it appears that the drag (C_{F_y}) reduction over configuration 1 is about 20 percent. The corresponding lateral force (C_{F_x}) reduction however is not quite this large.

5.4 Pressures on the MST

Appendix B, shows the pressure data organized by wind direction for the tap locations shown in Figures 4a to 4g. Table 1 shows the largest peak pressure coefficients measured on the MST. The largest peak pressure coefficient was 6.56 measured at tap 1099 for a wind angle of 135° . This location is near the roof edge where the adjacent taps also have very high suction values due to the separated flow in these regions. Most peak wall pressures are moderate values of about 3.0 magnitude with few locations exceeding this value. It must be remembered that these pressure coefficients are to be used with the full-scale hourly mean velocity at 30 ft. From Table 1 and the contour peak pressure plots of Figures 4l to 4s, it can be seen for corresponding taps and walls that the internal magnitudes are generally less than the external magnitudes.

5.5 Forces and Moments on the SSV

The force and moment coefficients on the six configurations of the SSV are shown in Table 2. Figure 13 graphs the M_x and M_y model values measured for configuration E-2. This shows that the maximum M_x and M_y values are for 190° wind angle. These magnitudes are somewhat higher than the 180° values.

Table f contains comparative values of the model forces and moments for configurations E-2₂ and E-2. As is expected, configuration E-2₂ has higher values than those of E-2. This is due, of course, to the fact that E-2₂ are measurements on the orbiter and tanks connected and E-2 was on the orbiter only. The reduction appears to be about a third. Note that the ratios of coefficients shown in Table 2 do not reflect a true difference in loads because of differing values of A and H used in the two coefficients (see section 4.4).

COMPARISON OF MODEL VALUES FOR CONFIGURATIONS E-2₂ AND E-2

E-2₂ = measurements on shuttle and tanks }
 E-2 = measurements on shuttle only } MST and PCR in place

Table f

Wind Angle	U _H ft/sec	E-2 ₂					E-2				
		F _x lbs	F _y lbs	M _x in/lbs	M _y in/lbs	M _z in/lbs	F _x lbs	F _y lbs	M _x in/lbs	M _y in/lbs	M _z in/lbs
90	27	-.00	-.01	.09	-.07	.01	-.01	-.00	.02	.02	.00
135	27	.01	-.01	.13	.07	.00	.00	-.01	.06	-.06	.00
180	27	-.12	-.09	1.83	-2.09	.20	-.10	-.07	.78	-1.50	-.02
225	27	-.13	-.02	.08	-2.46	.21	-.09	.01	.15	-1.17	-.02
270	27	-.02	.06	-.52	-.33	.03	-.01	.06	-.80	-.11	.01

Note: these are values measured in the model studies with similar reference velocities

The highest values in Table 2 correspond to configuration C which is that for the orbiter and tanks not enclosed by the MST and PCR. The largest value is 1.55 for a wind angle of 90° and - 1.46 for a 270° wind.

Configurations A, B and E-2₂ (have similar reference areas and lengths to configuration C) indicate the significant protection that the surrounding MST and PCR give to the orbiter and tanks.


Configuration D-2 represents measurements on the external tank only without the orbiter in place. If there were no surrounding buildings and this tank was positioned in boundary layer flow, a drag coefficient of about 1.2 might be expected. However, due to the protection given the external tank by the surrounding buildings, Table 2 gives a maximum drag of 0.20.

The magnitude of coefficients in Table 2, for configuration E-2, seems high at a first glance. However, as inspection of these numbers and the corresponding reference area (the frontal projection of SSV only) sheds light. If there were no surrounding structures to inhibit the flow, the SSV on its own might behave in a manner not dissimilar to that of a two-dimensional flat plate (drag coefficient of 1.3). The area adjoining the wings and the body of the orbiter appear to receive much wind load, especially in the vicinity of quartering winds of 225° . The maximum drag (C_{F_y}) of -0.73 with corresponding lateral force (C_{F_x}) of -1.04, thus appears reasonable.


REFERENCES

1. Cermak, J. E. "Laboratory simulation of the Atmospheric Boundary Layer," AIAA J1., Vol. 9, Sept. 1971.
2. Cermak, J. E. "Application of Fluid Mechanics to Wind Engineering," A Freeman Scholar Lecture, ASME J1 of Fluid Engineering, Vol. 97, No. 1, March 1975.
3. Cermak, J. E. "Aerodynamics of Buildings," Annual Review of Fluid Mechanics, Vol. 8, pp. 75-106, 1976.
4. American National Standard Institute,
"American National Standard Building Code Requirements
for Minimum Design Loads in Buildings and Other
Structures," ANSI Standard A58-1, 1972.
5. Velozzi, J. and Cohen, C.,
"Gust Response Factors," J1 Structural Div., ASCE,
Proc. Paper No. 5980, Vol. 94, No. ST6, 1968.

FIGURES



PLAN



All Dimensions in m

ELEVATION

Figure 1. Environmental Wind Tunnel
 Fluid Dynamics and Diffusion Laboratory
 Colorado State University





Figure 2. Tunnel Setup of MST



WIND ANGLE: α .

ORIGIN: MST--GROUND LEVEL
SSV--TOP OF LAUNCH MOUNT

MODEL SCALE - 1/100

TOTAL TAPS = 156

Figure 3. Coordinate System - MST




Figure 4a. MST - Pressure Taps




Figure 4b. MST - Pressure Taps




Figure 4c. MST - Pressure Taps




Figure 4d. MST - Pressure Taps




Figure 4e. MST - Pressure Taps




Figure 4f. MST - Pressure Taps




Figure 4g. MST- Pressure Taps




Figure 4h. MST - Pressure Model




Figure 4j. MST - Pressure Model




Figure 4k. Data Sampling Time Verification




Figure 41. Peak Pressure Contours - External




Figure 4m. Peak Pressure Contours - External




Figure 4n. Peak Pressure Contours - External




Figure 4p. Peak Pressure Contours - Internal




Figure 4q. Peak Pressure Contours - Internal





Figure 4r. Peak Pressure Contours - Internal



ROOF




Figure 4s. Peak Pressure Contours - Roof




Figure 5a. Two-Component Force Balance




Figure 5b. Two-Component Force Balance




Figure 5c. Two-Component Force Balance




Figure 5d. The Force Diagram of the Dynamometer




Figure 5e. Free Body Diagram 1




Figure 5f. Free Body Diagram 2




Figure 5g. Two-Component Force Balance Calibration



Figure 6a. Three-Component Moment Balance






Figure 6b. Three-Component Moment Balance



Notes

All spring steel plates are 1/2" wide. Horizontal strain gages used to measure M_x and M_y are numbered 5-10. Vertical strain gages used to measure M_z are numbered 1-4.



Horizontal spring steel plates on which the strain gages are mounted.

SECTION AA

Figure 6c. Three-Component Moment Balance




Figure 6d. Three-Component Moment Balance Calibration




Figure 7a. Configuration 1 - MST




Figure 7b. Configuration 1A - MST




Figure 7c. Configuration 2 - MST




Figure 7d. Configuration 3 - MST




Figure 7f. Configuration 5 - MST



Figure 7g. MST in Wind Tunnel (looking upstream)




Figure 8a. Configuration A - SSV




Figure 8aa. Configuration A - SSV




Figure 8b. Configuration B - SSV




Figure 8bb. Configuration B - SSV

Note: Configuration E similar except PCR Building moved further back 16 ft, 4 in. (away from launch pad).




Figure 8c. Configuration C - SSV




Figure 8cc. Configuration C - SSV




Figure 8d. configuration E-2₂ - SSV
(Orbiter and tanks connected)




Figure 8e. Configuration E-2 - SSV
(Orbiter disconnected from tanks)




Figure 8f. Configuration D-2 - SSV




Figure 9. Strategic Velocity Positions




Figure 10. Locations for Velocity Profiles

Graph # 1




Figure 11. Velocity and Turbulence Profiles

Graph # 2




Figure 12. Velocity and Turbulence Profiles




Figure 13. Location of Wind Angle to Give Maximum Moments on SSV

TABLES

Table 1. MST Cladding Loads - Configuration 5 - Mobile Service Tower (MST) Largest Value of ABS(CPMAX) or ABS(CPMAX), Peak Load Reference Pressure = 1 PSF

TAP	AZI-MUTH	PRESS COEFF	PEAK LOAD (PSF)	TAP	AZI-MUTH	PRESS COEFF	PEAK LOAD (PSF)	TAP	AZI-MUTH	PRESS COEFF	PEAK LOAD (PSF)
10001	90	3.00	3.00	10501	270	2.42	2.42	20001	270	2.21	2.21
10002	90	0.04	0.04	10502	270	1.59	1.59	20002	180	2.21	2.21
10003	90	0.48	0.48	10503	180	1.45	1.45	20003	180	1.22	1.22
10004	90	0.97	0.97	10504	180	0.92	0.92	20004	180	0.21	0.21
10005	90	0.63	0.63	10505	180	1.16	1.16	20005	180	0.15	0.15
10006	270	0.22	0.22	10506	270	0.25	0.25	20006	90	0.22	0.22
10007	270	0.75	0.75	10507	270	0.25	0.25	20008	90	0.22	0.22
10008	270	0.40	0.40	10508	90	1.19	1.19	20010	270	0.42	0.42
10009	90	0.60	0.60	10509	90	0.34	0.34	20012	270	0.39	0.39
10100	90	0.68	0.68	10600	270	0.68	0.68	20014	270	0.72	0.72
10101	270	0.29	0.29	10601	270	0.33	0.33	20016	270	0.39	0.39
10102	270	0.88	0.88	10602	90	0.44	0.44	20018	180	0.11	0.11
10103	270	0.30	0.30	10603	90	0.49	0.49	20020	90	0.00	0.00
10104	90	0.90	0.90	10604	270	0.80	0.80	20022	180	0.00	0.00
10105	270	0.05	0.05	10605	270	0.66	0.66	20024	90	0.33	0.33
10106	270	0.64	0.64	10606	90	0.99	0.99	20026	90	0.00	0.00
10107	270	0.57	0.57	10607	90	0.29	0.29	20027	90	0.00	0.00
10108	90	0.31	0.31	10608	270	0.22	0.22	20029	90	0.00	0.00
10109	270	0.70	0.70	10609	270	0.22	0.22	20031	270	0.11	0.11
10200	270	0.30	0.30	10700	90	0.68	0.68	20032	270	0.66	0.66
10201	270	0.11	0.11	10701	90	0.35	0.35	20033	270	0.44	0.44
10202	270	0.28	0.28	10702	90	0.36	0.36	20035	270	0.66	0.66
10203	270	0.18	0.18	10703	44	0.33	0.33	20037	270	0.44	0.44
10204	270	0.86	0.86	10704	90	0.00	0.00	20039	270	0.00	0.00
10205	270	0.26	0.26	10705	90	0.00	0.00	20041	270	0.00	0.00
10206	180	0.60	0.60	10706	90	0.00	0.00	20043	270	0.00	0.00
10207	180	0.20	0.20	10707	90	0.22	0.22	20044	180	0.00	0.00
10208	180	0.12	0.12	10708	90	0.66	0.66	20047	180	0.00	0.00
10209	180	0.59	0.59	10800	90	0.44	0.44	20048	180	0.00	0.00
10210	180	0.66	0.66	10801	90	0.71	0.71	20049	180	0.00	0.00
10211	180	0.34	0.34	10802	90	0.44	0.44	20050	180	0.00	0.00
10212	180	0.64	0.64	10803	44	0.44	0.44	20051	180	0.00	0.00
10213	180	0.55	0.55	10804	44	0.44	0.44	20053	180	0.00	0.00
10214	180	0.45	0.45	10805	44	0.44	0.44	20055	180	0.00	0.00
10215	180	0.58	0.58	10806	90	0.44	0.44	20057	180	0.00	0.00
10216	180	0.58	0.58	10807	270	0.22	0.22	20059	180	0.00	0.00
10217	180	0.58	0.58	10808	270	0.44	0.44	20061	180	0.00	0.00
10218	180	0.71	0.71	10809	270	0.22	0.22	20063	180	0.00	0.00
10219	180	0.00	0.00	10900	270	0.33	0.33	20065	180	0.00	0.00
10220	180	0.96	0.96	10901	270	0.00	0.00	20067	180	0.00	0.00
10221	180	0.47	0.47	10902	270	0.00	0.00	20069	180	0.00	0.00
10222	180	0.78	0.78	10903	270	0.00	0.00	20071	180	0.00	0.00
10223	180	0.53	0.53	10904	270	0.00	0.00	20073	180	0.00	0.00
10224	180	0.77	0.77	10905	270	0.00	0.00	20075	180	0.00	0.00
10225	180	0.15	0.15	10906	270	0.00	0.00	20076	180	0.00	0.00
10226	180	0.68	0.68	10907	270	0.00	0.00	20077	180	0.00	0.00
10227	180	0.03	0.03	10908	270	0.00	0.00	20078	180	0.00	0.00
10228	180	0.12	0.12	10909	270	0.00	0.00	20079	180	0.00	0.00
10229	180	0.47	0.47	11000	270	0.00	0.00	20080	180	0.00	0.00
20081	270	0.15	0.15	20086	270	0.00	0.00	20096	270	0.11	0.11
20082	270	0.06	0.06	20090	270	0.00	0.00	20097	270	0.07	0.07
20083	270	0.23	0.23	20091	270	0.00	0.00	20099	270	0.16	0.16
20084	270	0.14	0.14	20095	270	0.00	0.00	21000	270	0.00	0.00

Table 2. Forces and Moments on Space Shuttle (SSV)

Configuration	Wind Angle	C_{F_x}	C_{F_y}	C_{M_x}	C_{M_y}	C_{M_z}	
MST and AT	A	90	.00	.00	.00	.00	
	A	135	.03	.00	.00	-.04	
	A	180	.00	.00	.00	.07	
	A	225	-.26	-.03	+.04	-.08	.29
	A	270	-.03	.03	-.01	.01	.02
MST AT and PCR (close)	B	90	-.03	-.03	+.01	-.01	.02
	B	135	.03	-.03	+.01	-.01	-.02
	B	180	-.18	-.34	+.15	-.08	-.16
	B	225	.49	.03	-.01	.21	.35
	B	270	-.06	.13	-.03	-.04	.06
AT only	C	90	-.07	1.55	-.66	-.05	.13
	C	135	.52	1.02	-.31	-.35	.82
	C	180	-.53	-.29	+.20	-.29	.41
	C	225	-.93	-.80	+.46	-.49	.45
	C	270	-.29	-1.46	+.75	-.09	-.09
MST AT and PCR (moved back from SSV)	E-2 ₂	90	.00	.03	+.01	-.01	.02
	E-2 ₂	135	.03	-.03	+.01	.00	.00
	E-2 ₂	180	-.47	-.34	+.18	-.17	.50
	E-2 ₂	225	-.50	.06	+.01	-.23	.52
	E-2 ₂	270	-.06	.19	-.05	-.03	.06

Table 2 (continued)

Configuration	Wind Angle	C_{F_x}	C_{F_y}	C_{M_x}	C_{M_y}	C_{M_z}
E-2	90	-.10	-.03	.02	.02	.00
Shuttle Not Connected to External Tanks	135	.03	-.10	.05	-.05	.00
	170	---	---	.08	-.31	.14
	180	-1.04	-.73	.10	-.48	-.14
Measurements on Shuttle Only	190	---	---	.13	-.53	-.28
	200	---	---	.10	-.45	-.21
	225	-.93	.10	.05	-.29	-.14
	270	-.10	.62	-.21	-.02	-.07
D-2	90	-.05	-.04	.01	.01	.00
Measurements on External Tank Only	135	.03	-.04	.01	.01	.00
	180	-.10	-.11	.02	.07	.00
	225	-.20	.12	.04	.06	.00
	270	-.04	.06	.01	.01	.00

--- No measurement

Note: Where the coefficients listed in Table 2, page 90 are less than about 0.03, the corresponding voltage readings were less than about 5-10 mV. Any voltage readings below these are considered to be at the lower bounds of probable values and hence such coefficients given are to be used only as approximate estimates of true values.

Table 3. Wind Velocites and Turbulence Intensities
SSV - Configuration B

Key: 1V means the y-z plane velocity components at location 1
1H means the horizontal velocity components at location 2
 U_H = velocity at building height = U_{272} (full scale)

WIND AZIMUTH	U_{mean}/U_H (percent)	U_{rms}/U_H (percent)	U_{peak}/U_H (percent)
<u>Location 1V</u>			
90.00	15.6	5.4	31.8
135.00	19.8	5.2	35.4
180.00	18.4	5.0	33.4
225.00	33.8	4.1	46.1
270.00	49.9	6.8	70.3
<u>Location 1H</u>			
90.00	20.7	8.6	46.5
135.00	26.5	8.4	51.7
180.00	29.8	8.1	54.1
225.00	85.8	7.5	108.3
270.00	54.5	7.3	76.5
<u>Location 2V</u>			
90.00	29.5	8.8	55.9
135.00	17.0	5.4	33.2
180.00	29.2	8.9	55.9
225.00	39.0	14.2	81.6
270.00	55.7	7.2	77.3
<u>Location 2H</u>			
90.00	20.8	4.2	33.4
135.00	15.4	4.2	28.0
180.00	33.3	11.2	66.9
225.00	29.0	9.8	58.4
270.00	24.5	3.5	35.0
<u>Location 3V</u>			
90.00	18.8	8.0	42.8
135.00	26.9	6.8	47.3
180.00	21.5	8.3	46.4
225.00	80.1	14.9	124.8
270.00	74.2	15.5	120.7
<u>Location 3H</u>			

Table 3 (continued)

WIND AZIMUTH	U_{mean}/U_H (percent)	U_{rms}/U_H (percent)	U_{peak}/U_H (percent)
<u>Location 3H</u>			
90.00	18.7	7.3	40.6
135.00	25.3	7.5	47.8
180.00	23.7	8.0	47.7
225.00	73.4	17.5	125.9
270.00	64.0	17.1	115.3
<u>Location 4V</u>			
90.00	71.2	6.0	89.2
135.00	55.0	4.1	67.3
180.00	27.6	11.8	63.0
225.00	82.1	10.7	114.2
270.00	102.5	9.4	130.7
<u>Location 4H</u>			
90.00	52.3	3.6	63.1
135.00	50.0	4.2	62.6
180.00	15.7	6.2	34.3
225.00	44.2	7.2	65.8
270.00	55.9	5.6	72.7
<u>Location 5V</u>			
90.00	63.5	19.2	121.1
135.00	63.8	16.2	112.4
180.00	15.2	5.3	31.1
225.00	58.2	18.6	114.0
270.00	82.0	23.9	153.7
<u>Location 5H</u>			
90.00	51.8	12.5	89.3
135.00	49.4	9.6	78.2
180.00	9.0	2.7	17.1
225.00	27.7	10.9	60.4
270.00	40.1	15.7	87.2
<u>Location 6V</u>			
90.00	12.7	3.3	22.6
135.00	20.4	6.2	39.0
180.00	16.8	4.9	31.5
225.00	27.7	10.2	58.3
270.00	39.6	12.8	78.0

Table 3 (continued)

WIND AZIMUTH	U_{mean}/U_H (percent)	U_{rms}/U_H (percent)	U_{peak}/U_H (percent)
<u>Location 6H</u>			
90.00	12.2	3.1	21.5
135.00	16.8	4.4	30.0
180.00	18.2	5.2	33.8
225.00	24.0	8.0	48.0
270.00	24.8	6.5	44.3

APPENDIX A

APPENDIX A

 * FORCE AND MOMENT COEFFICIENTS FOR M.S.T. BUILDING CONFIG ONE *
 * ---COEFFICIENTS TO BE USED WITH FULL SCALE WIND VELOCITY AT 30 FEET--- *

WIND DIRECTION = 90

CFX	CFY	CMX	CMY	CMZ
-0.05	2.25	-1.04	-0.07	-0.00

WIND DIRECTION = 135

CFX	CFY	CMX	CMY	CMZ
1.19	1.95	-0.87	1.01	-0.04

WIND DIRECTION = 180

CFX	CFY	CMX	CMY	CMZ
1.86	0.02	0.21	1.41	-0.01

WIND DIRECTION = 225

CFX	CFY	CMX	CMY	CMZ
1.92	-1.53	1.09	1.42	-0.00

WIND DIRECTION = 270

CFX	CFY	CMX	CMY	CMZ
0.13	-2.36	1.48	0.05	-0.00

APPENDIX A

 * FORCE AND MOMENT COEFFICIENTS FOR M.S.T. BUILDING CONFIG ONE A *
 * ---COEFFICIENTS TO BE USED WITH FULL SCALE WIND VELOCITY AT 30 FEET--- *

WIND DIRECTION = 90

CFX	CFY	CMX	CMY	CMZ
-0.02	2.26	-1.01	-0.03	.00

WIND DIRECTION = 135

CFX	CFY	CMX	CMY	CMZ
1.41	1.98	-0.85	1.14	-0.04

WIND DIRECTION = 180

CFX	CFY	CMX	CMY	CMZ
1.86	-0.06	.27	1.48	-0.02

WIND DIRECTION = 225

CFX	CFY	CMX	CMY	CMZ
1.95	-1.43	1.11	1.52	-0.01

WIND DIRECTION = 270

CFX	CFY	CMX	CMY	CMZ
.10	-1.97	1.35	.05	-0.01

APPENDIX A

 *
 * FORCE AND MOMENT COEFFICIENTS FOR M.S.T. BUILDING CONFIG TWO *
 * ---COEFFICIENTS TO BE USED WITH FULL SCALE WIND VELOCITY AT 30 FEET--- *
 *

WIND DIRECTION = 90				
CFX	CFY	CMX	CMY	CMZ
.01	2.08	-.93	-.01	.00
WIND DIRECTION = 135				
CFX	CFY	CMX	CMY	CMZ
1.25	1.90	-.80	1.00	-.04
WIND DIRECTION = 180				
CFX	CFY	CMX	CMY	CMZ
1.87	.06	-.06	1.41	-.01
WIND DIRECTION = 225				
CFX	CFY	CMX	CMY	CMZ
1.83	-1.34	.87	1.42	-.02
WIND DIRECTION = 270				
CFX	CFY	CMX	CMY	CMZ
-.05	-1.96	1.12	.04	-.01

APPENDIX A

* FORCE AND MOMENT COEFFICIENTS FOR M.S.T. BUILDING CONFIG THREE *
* ---COEFFICIENTS TO BE USED WITH FULL SCALE WIND VELOCITY AT 30 FEET--- *

WIND DIRECTION = 90

CFX	CFY	CMX	CMY	CMZ
.03	1.72	-.74	.01	.00

WIND DIRECTION = 135

CFX	CFY	CMX	CMY	CMZ
2.02	1.44	-.56	1.41	-.00

WIND DIRECTION = 180

CFX	CFY	CMX	CMY	CMZ
1.77	.17	.12	1.43	-.02

WIND DIRECTION = 225

CFX	CFY	CMX	CMY	CMZ
2.44	-.90	.72	1.73	-.04

WIND DIRECTION = 270

CFX	CFY	CMX	CMY	CMZ
-.01	-1.41	.98	.09	-.00

APPENDIX A

 * FORCE AND MOMENT COEFFICIENTS FOR M.S.T. BUILDING CONFIG FOUR *
 * ---COEFFICIENTS TO BE USED WITH FULL SCALE WIND VELOCITY AT 30 FEET--- *

WIND DIRECTION = 90

CFX	CFY	CMX	CMY	CMZ
.03	1.78	-.77	.00	.00

WIND DIRECTION = 135

CFX	CFY	CMX	CMY	CMZ
1.57	1.60	-.59	1.23	-.03

WIND DIRECTION = 180

CFX	CFY	CMX	CMY	CMZ
1.83	.13	.13	1.41	-.02

WIND DIRECTION = 225

CFX	CFY	CMX	CMY	CMZ
1.93	-.87	.66	1.40	-.03

WIND DIRECTION = 270

CFX	CFY	CMX	CMY	CMZ
-.05	-1.71	1.04	.03	-.00

APPENDIX A

 * FORCE AND MOMENT COEFFICIENTS FOR M.S.T. BUILDING CONFIG FIVE *
 * ---COEFFICIENTS TO BE USED WITH FULL SCALE WIND VELOCITY AT 30 FEET--- *

WIND DIRECTION = 90

CFX	CFY	CMX	CMY	CMZ
-0.01	1.94	-0.87	-0.01	.00

WIND DIRECTION = 135

CFX	CFY	CMX	CMY	CMZ
1.17	1.59	-0.75	.87	-0.04

WIND DIRECTION = 180

CFX	CFY	CMX	CMY	CMZ
1.67	-0.14	.19	1.20	-0.00

WIND DIRECTION = 225

CFX	CFY	CMX	CMY	CMZ
1.75	-1.50	1.01	1.31	-0.01

WIND DIRECTION = 270

CFX	CFY	CMX	CMY	CMZ
-0.05	-1.98	1.37	.07	-0.01

APPENDIX B

APPENDIX B -- PRESSURE DATA: MOBILE SERVICE TOWER (M.S.T.)

WD	TAP	CPMEAN	CPRMS	CPMAX	CPMIN	WD	TAP	CPMEAN	CPRMS	CPMAX	CPMIN	WD	TAP	CPMEAN	CPRMS	CPMAX	CPMIN
180	2043	2260	2233	2255	2225	2225	1015	2265	2225	2255	2217	1065	2722	217	2255	1031	544
180	2044	2201	2231	2255	2225	2225	1016	2419	2236	2266	2210	1066	2722	204	2255	1274	169
180	2047	2282	2233	2255	2225	2225	1017	2244	2225	2266	2210	1067	2722	234	2255	1509	079
180	2048	2215	2233	2255	2225	2225	1018	2045	2233	2266	2210	1068	2722	296	2233	456	096
180	2049	2344	2231	2255	2225	2225	1019	2185	2244	2266	2210	1069	2722	278	2222	912	499
180	2050	2005	2231	2255	2225	2225	1020	2345	2249	2266	2210	1070	2722	531	2231	1448	216
180	2051	2287	2232	2255	2225	2225	1021	2150	2231	2266	2210	1071	2722	757	2259	1770	006
180	2053	2291	2232	2255	2225	2225	1022	2990	2242	2266	2210	1072	2722	462	2263	372	459
180	2055	2285	2232	2255	2225	2225	1023	2129	2247	2266	2210	1073	2722	101	2261	856	799
180	2057	2071	2232	2255	2225	2225	1024	2345	2258	2266	2210	1074	2722	459	2245	1196	247
180	2059	2198	2232	2255	2225	2225	1025	2160	2232	2266	2210	1075	2722	613	2242	1416	168
180	2061	2262	2232	2255	2225	2225	1026	2232	2201	2266	2210	1076	2722	110	2230	858	407
180	2063	2261	2232	2255	2225	2225	1027	2260	2210	2266	2210	1077	2722	187	2261	1081	304
180	2065	2191	2232	2255	2225	2225	1028	2319	2225	2266	2210	1078	2722	059	2233	839	223
180	2067	2299	2232	2255	2225	2225	1029	2114	2210	2266	2210	1079	2722	018	2230	1734	227
180	2069	2236	2232	2255	2225	2225	1030	2098	2210	2266	2210	1080	2722	059	2243	1620	091
180	2071	2222	2232	2255	2225	2225	1031	2165	2210	2266	2210	1081	2722	626	2248	844	752
180	2073	2222	2232	2255	2225	2225	1032	2350	2207	2266	2210	1082	2722	777	2258	932	754
180	2075	2222	2232	2255	2225	2225	1033	2350	2211	2266	2210	1083	2722	777	2258	932	754
180	2077	2222	2232	2255	2225	2225	1034	2350	2213	2266	2210	1084	2722	777	2258	932	754
180	2079	2222	2232	2255	2225	2225	1035	2269	2219	2266	2210	1085	2722	777	2258	932	754
180	2080	2222	2232	2255	2225	2225	1036	2295	2215	2266	2210	1086	2722	777	2258	932	754
180	2082	2237	2232	2255	2225	2225	1037	2223	2201	2266	2210	1087	2722	777	2258	932	754
180	2084	2237	2232	2255	2225	2225	1038	2223	2201	2266	2210	1088	2722	777	2258	932	754
180	2085	2237	2232	2255	2225	2225	1039	2223	2201	2266	2210	1089	2722	777	2258	932	754
180	2086	2237	2232	2255	2225	2225	1040	2407	2213	2266	2210	1090	2722	777	2258	932	754
180	2088	2237	2232	2255	2225	2225	1041	2185	2213	2266	2210	1091	2722	777	2258	932	754
180	2090	2237	2232	2255	2225	2225	1042	2127	2205	2266	2210	1092	2722	777	2258	932	754
180	2091	2237	2232	2255	2225	2225	1043	2188	2214	2266	2210	1093	2722	777	2258	932	754
180	2093	2237	2232	2255	2225	2225	1044	2122	2209	2266	2210	1094	2722	777	2258	932	754
180	2095	2237	2232	2255	2225	2225	1045	2221	2216	2266	2210	1095	2722	777	2258	932	754
180	2097	2237	2232	2255	2225	2225	1046	2331	2224	2266	2210	1096	2722	777	2258	932	754
180	2099	2237	2232	2255	2225	2225	1047	2095	2210	2266	2210	1097	2722	777	2258	932	754
180	2100	2237	2232	2255	2225	2225	1048	2041	2227	2266	2210	1098	2722	777	2258	932	754
225	1001	2344	2232	2255	2225	2225	1049	2085	2237	2266	2210	1099	2722	777	2258	932	754
225	1002	2344	2232	2255	2225	2225	1050	2059	2235	2266	2210	1100	2722	777	2258	932	754
225	1003	2344	2232	2255	2225	2225	1051	2142	2229	2266	2210	2001	2722	777	2258	932	754
225	1004	2344	2232	2255	2225	2225	1052	2297	2239	2266	2210	2002	2722	777	2258	932	754
225	1005	2344	2232	2255	2225	2225	1053	2073	2219	2266	2210	2003	2722	777	2258	932	754
225	1006	2344	2232	2255	2225	2225	1054	2004	2229	2266	2210	2004	2722	777	2258	932	754
225	1007	2344	2232	2255	2225	2225	1055	2040	2241	2266	2210	2005	2722	777	2258	932	754
225	1008	2344	2232	2255	2225	2225	1056	2252	2240	2266	2210	2006	2722	777	2258	932	754
225	1009	2344	2232	2255	2225	2225	1057	2150	2219	2266	2210	2007	2722	777	2258	932	754
225	1010	2344	2232	2255	2225	2225	1058	2328	2231	2266	2210	2008	2722	777	2258	932	754
225	1011	2344	2232	2255	2225	2225	1059	2580	2254	2266	2210	2009	2722	777	2258	932	754
225	1012	2344	2232	2255	2225	2225	1060	2241	2232	2266	2210	2010	2722	777	2258	932	754
225	1013	2344	2232	2255	2225	2225	1061	2317	2236	2266	2210	2011	2722	777	2258	932	754
225	1014	2344	2232	2255	2225	2225	1062	2616	2222	2266	2210	2012	2722	777	2258	932	754
225	1015	2344	2232	2255	2225	2225	1063	2905	2248	2266	2210	2013	2722	777	2258	932	754
225	1016	2344	2232	2255	2225	2225	1064	2342	2229	2266	2210	2014	2722	777	2258	932	754
225	1017	2344	2232	2255	2225	2225	1065	2417	2225	2266	2210	2015	2722	777	2258	932	754
225	1018	2344	2232	2255	2225	2225	1066	2664	2225	2266	2210	2016	2722	777	2258	932	754
225	1019	2344	2232	2255	2225	2225	1067	2491	2225	2266	2210	2017	2722	777	2258	932	754
225	1020	2344	2232	2255	2225	2225	1068	2300	2225	2266	2210	2018	2722	777	2258	932	754
225	1021	2344	2232	2255	2225	2225	1069	2414	2225	2266	2210	2019	2722	777	2258	932	754
225	1022	2344	2232	2255	2225	2225	1070	2574	2225	2266	2210	2020	2722	777	2258	932	754
225	1023	2344	2232	2255	2225	2225	1071	2376	2225	2266	2210	2021	2722	777	2258	932	754
225	1024	2344	2232	2255	2225	2225	1072	2034	2225	2266	2210	2022	2722	777	2258	932	754
225	1025	2344	2232	2255	2225	2225	1073	2212	2225	2266	2210	2023	2722	777	2258	932	754
225	1026	2344	2232	2255	2225	2225	1074	2445	2225	2266	2210	2024	2722	777	2258	932	754
225	1027	2344	2232	2255	2225	2225	1075	2326	2225	2266	2210	2025	2722	777	2258	932	754
225	1028	2344	2232	2255	2225	2225	1076	2602	2225	2266	2210	2026	2722	777	2258	932	754
225	1029	2344	2232	2255	2225	2225	1077	2511	2225	2266	2210	2027	2722	777	2258	932	754
225	1030	2344	2232	2255	2225	2225	1078	2469	2225	2266	2210	2028	2722	777	2258	932	754
225	1031	2344	2232	2255	2225	2225	1079	2285	2225	2266	2210	2029	2722	777	2258	932	754
225	1032	2344	2232	2255	2225	2225	1080	2439	2225	2266	2210	2030	2722	777	2258	932	754
225	1033	2344	2232	2255	2225	2225	1081	2539	2225	2266	2210	2031	2722	777	2258	932	754
225	1034	2344	2232	2255	2225	2225	1082	2678	2225	2266	2210	2032	2722	777	2258	932	754
225	1035	2344	2232	2255	2225	2225	1083	2640	2225	2266	2210	2033	2722	777	2258	932	754
225	1036	2344	2232	2255	2225	2225	1084	2556	2225	2266	2210	2034	2722	777	2258	932	754
225	1037	2344	2232	2255	2225	2225	1085	2600	2225	2266	2210	2035	2722	777	2258	932	754
225	1038	2344	2232	2255	2225	2225	1086	2658	2225	2266	2210	2036	2722	777	2258	932	754
225	1039	2344	2232	2255	2225	2225	1087	2658	2225	2266	2210	2037	2722	777	2258	932	754
225	1040	2344	2232	2255	2225	2225	1088	2708	2225	2266	2210	2038	2722	777	2258	932	754
225	1041	2344	2232	2255	2225	2											

APPENDIX B -- PRESSURE DATA: MOBILE SERVICE TOWER (M.S.T.)

WD	TAP	CPMAX	CPRMS	CPMEAN	CPMIN	WD	TAP	CPMAX	CPRMS	CPMEAN	CPMIN	WD	TAP	CPMAX	CPRMS	CPMEAN	CPMIN
2270	2024	144	512	76	955	2270	1003	824	312	824	131	2270	1053	261	385	261	172
2270	2026	1.208	833	63	401	2270	1004	1.612	350	1.612	931	2270	1054	267	385	267	188
2270	2027	875	263	73	021	2270	1005	1.210	578	1.210	113	2270	1055	267	385	267	274
2270	2029	761	234	87	049	2270	1006	1.482	397	1.482	217	2270	1056	261	385	261	500
2270	2031	928	246	82	021	2270	1007	1.765	427	1.765	751	2270	1057	403	367	403	217
2270	2032	1.204	280	44	038	2270	1008	1.819	425	1.819	398	2270	1058	403	367	403	772
2270	2035	539	240	25	333	2270	1009	1.386	328	1.386	468	2270	1059	313	696	313	794
2270	2036	778	227	52	333	2270	1010	1.495	335	1.495	962	2270	1060	439	537	439	680
2270	2037	928	231	66	355	2270	1011	1.649	354	1.649	286	2270	1061	352	396	352	928
2270	2038	862	269	82	400	2270	1012	1.707	432	1.707	884	2270	1062	309	459	309	581
2270	2039	644	247	62	400	2270	1013	1.673	448	1.673	304	2270	1063	304	446	304	612
2270	2041	942	222	77	626	2270	1014	1.433	323	1.433	608	2270	1064	439	186	439	802
2270	2043	1.115	249	87	626	2270	1015	1.605	365	1.605	648	2270	1065	337	453	337	257
2270	2044	673	248	40	350	2270	1016	1.806	446	1.806	638	2270	1066	337	453	337	173
2270	2047	742	228	88	444	2270	1017	1.622	463	1.622	666	2270	1067	401	513	401	226
2270	2048	243	117	43	444	2270	1018	1.496	308	1.496	947	2270	1068	401	153	401	358
2270	2049	857	243	87	333	2270	1019	1.650	343	1.650	133	2270	1069	422	673	422	420
2270	2050	620	39	43	333	2270	1020	1.821	394	1.821	304	2270	1070	422	673	422	882
2270	2051	621	319	43	333	2270	1021	1.652	382	1.652	300	2270	1071	401	623	401	651
2270	2053	738	32	44	444	2270	1022	1.599	399	1.599	799	2270	1072	331	444	331	166
2270	2055	796	45	86	444	2270	1023	1.685	380	1.685	181	2270	1073	331	385	331	147
2270	2057	730	57	99	444	2270	1024	1.289	305	1.289	863	2270	1074	331	298	331	897
2270	2059	844	36	33	444	2270	1025	1.190	286	1.190	265	2270	1075	331	566	331	997
2270	2061	882	41	11	444	2270	1026	1.304	276	1.304	287	2270	1076	331	817	331	180
2270	2063	808	26	99	444	2270	1027	1.455	276	1.455	556	2270	1077	331	817	331	410
2270	2065	926	51	30	444	2270	1028	1.269	264	1.269	267	2270	1078	331	808	331	666
2270	2067	771	35	24	444	2270	1029	1.235	294	1.235	251	2270	1079	331	808	331	219
2270	2069	877	38	32	444	2270	1030	1.311	298	1.311	51	2270	1080	331	159	331	861
2270	2071	746	16	44	444	2270	1031	1.312	328	1.312	229	2270	1081	331	557	331	804
2270	2073	861	36	51	444	2270	1032	1.232	305	1.232	441	2270	1082	331	703	331	751
2270	2075	014	26	69	444	2270	1033	1.189	328	1.189	141	2270	1083	331	713	331	612
2270	2076	983	36	53	444	2270	1034	1.131	247	1.131	024	2270	1084	331	306	331	054
2270	2077	951	36	67	444	2270	1035	1.137	337	1.137	043	2270	1085	331	294	331	943
2270	2078	935	15	44	444	2270	1036	1.212	355	1.212	437	2270	1086	331	355	331	030
2270	2080	907	23	33	444	2270	1037	1.198	355	1.198	550	2270	1087	331	444	331	318
2270	2081	755	46	62	444	2270	1038	1.198	355	1.198	055	2270	1088	331	444	331	855
2270	2082	770	22	22	444	2270	1039	1.193	355	1.193	055	2270	1089	331	444	331	807
2270	2084	814	53	40	444	2270	1040	1.029	263	1.029	348	2270	1090	331	600	331	675
2270	2085	830	42	14	444	2270	1041	1.979	240	1.979	013	2270	1091	331	557	331	897
2270	2086	761	52	06	444	2270	1042	1.185	314	1.185	559	2270	1092	331	643	331	217
2270	2090	835	49	05	444	2270	1043	1.304	320	1.304	227	2270	1093	331	539	331	832
2270	2091	835	12	24	444	2270	1044	1.316	314	1.316	996	2270	1094	331	539	331	299
2270	2095	858	23	38	444	2270	1045	1.391	291	1.391	448	2270	1095	331	539	331	286
2270	2096	842	19	33	444	2270	1046	1.212	268	1.212	100	2270	1096	331	474	331	005
2270	2097	765	22	33	444	2270	1047	1.307	303	1.307	459	2270	1097	331	621	331	242
2270	2099	770	14	06	444	2270	1048	1.482	306	1.482	339	2270	1098	331	212	331	061
2270	2100	863	32	37	444	2270	1049	1.232	306	1.232	399	2270	1099	331	386	331	736
2270	1001	1.126	33	28	444	2270	1050	1.232	306	1.232	399	2270	1100	331	135	331	949
2270	1002	1.107	33	28	444	2270	1051	1.232	306	1.232	399	2270	2001	233	206	233	414
2270						2270	1052	1.512	279	1.512	587	2270	2002	1	3	1	290

